NOTE:

This SWMR was prepared in accordance with the Unified Sustainable Development Ordinance.

STORM WATER MANAGEMENT REPORT (SWMR)

90 State Street Apartment Conversion 90 State Street

CITY OF ALBANY COUNTY OF ALBANY STATE OF NEW YORK

Applicant: Harmony Mill South, LLC

PREPARED BY:

HERSHBERG & HERSHBERG



CONSULTING ENGINEERS

18 Locust Street
Albany, NY 12203-2908
Phone 518-459-3096
Fax 518-459-5683
Email hhershberg@aol.com

October 31, 2017

Table of Contents

Introduction	1
Description of Existing Site	1
Description of Intended Site Development and Use	2
Sewer System	2
Design Considerations	3
Summary	4
Conclusion & Cartification	1

Appendices

Appendix #1 – HydroCAD® 10.00 Calculations

Appendix #2 – Maintenance Plan

Appendix #3 – Maintenance Agreement

Appendix #4 – Detail of Roof Drains

Map Pockets

Map Pocket #1 - Existing Conditions and Sewer Connection Permit Plan - Sheet C-1

INTRODUCTION:

Hershberg & Hershberg, Consulting Engineers and Land Surveyors, were retained by Harmony Mill South, LLC (hereinafter the "Applicant") to review storm drainage for the proposed 90 State Street Apartment Conversion. This report is for the consideration of the Department of Water & Water Supply and the City of Albany Planning Board.

DESCRIPTION OF EXISTING SITE:

The existing parcel is Tax Map Parcel #76.42-1-5 listed as No. 90 State Street with a site area of 16,976 SF or 0.39 Acres. It is entirely occupied by a 15 story building.




Fig. No. 1 - Aerial Photo of Site

DESCRIPTION OF INTENDED SITE DEVELOPMENT AND USE

Under the current application the Applicant is proposing to convert floors 4 through 12, 14 & 15 from office space to 154 apartments which would have 176 bedrooms. The existing uses on the Ground floor through the 3rd floor will remain. They include a banquet hall, fast food, retail, personal services and offices.

SEWER SYSTEM

The storm drainage from this site is tributary to a Central Area Sewer District as shown on the portion Sewer Atlas Sheet 31 reproduced below.




Fig. No. 2 – Portion of Sewer Atlas Sheet 31

The 4'6" diameter sewer is tributary to a 6' diameter sewer before entering a regulating chamber which control flows to the Intercepting Sewer. When the set amount of flow is exceeded the combined sewer discharges into a system constructed by New York State in connection with the construction of Interstate 787. When the system overflows it creates a Combined Sewer Overflow to the Hudson River. This site is within the Combined Sewer Overlay (CS-O) District. Blue Roofs are a permitted method in the Unified Sustainable Development Ordinance.

The sewer system is well equipped to accommodate storm water flows from small storms. The Applicant proposes to use slow release roof drains to control the outfall generated by roof drainage for all storms. See detail in Appendix 4. This is the "blue roof" solution considered as an acceptable method according to the Uniform Sustainable Development Ordinance and is recognized in §375-2(f)(4)(d)(i)(B).

In the order to determine the net impact of adding sanitary flow while reducing storm sewer from the one-year storm has been analyzed. Compared to the site in its totally unpaved condition the discharge from the developed site is reduced from 0.26 CFS to 0.19 CFS which is reduction of 0.07 CFS. For the 10-year storm the change in storm flow from the site in its totally unpaved condition to the discharge from the developed site is reduced from 1.04 CFS to 0.47 CFS which is reduction of 0.57 CFS. It should be noted that the actual reduction in flow from the existing condition is from 1.25 CFS to 0.19 CFS for the one-year storm and from 2.42 CFS to 0.47 CFS for the 10-year storm. These results are shown below in Fig. No.3.

	I Year Storm	10 Year Storm
Condition Analyzed	Discharge	Discharge
	(CFS)	(CFS)
Pre Development (Totally Green)	0.26	1.04
Pre Development (Existing Cond.)	1.25	2.42
Post Development	0.19	0.47

Fig. No. 3 – Pre & Post HydroCAD Results

DESIGN CONSIDERATIONS:

The design of the SWMR for the subject site considered the following critical factors:

- 1. Compliance with Section 375-4(G)(11) of the Unified Sustainable Development Ordinance entitled STORMWATER MANAGEMENT which includes:
 - (d) The maximum allowable design peak-flow stormwater discharge into the combined sewer system shall be limited to the calculated peak-flow discharge of the **10-year storm for un-development site conditions**, as determined by

a Professional Engineer, and to be reviewed and accepted by the Department

of Water and Water Supply. (emphasis added)

SUMMARY:

The following is a summary of the findings of this study as presented by the preparer of this

report:

1. The permanent system complies with Section 375-4(G)(11) of the Unified

Sustainable Development Ordinance entitled STORMWATER

MANAGEMENT.

CONCLUSION & CERTIFICATION:

It is the conclusion of the Engineer that the erosion and sediment control system, as

designed, and the permanent storage and treatment system will function adequately to

clean the stormwater prior to discharge. Also, the Engineer certifies that the project will not

adversely impact adjacent or downstream properties or the downstream sewer collection

system.

LICENSED THE COLUMN TO THE PROPERTY OF NEW PORTS OF A 1226 MAY SO A 1226


Prepared by:

Daniel R. Hershberg, P.E. & L.S.

Lic. No. 44226

File:DRH/SWMR/SWMR20170316.DOC

APPENDIX #1 HYDROCAD® 10.00 CALCULATIONS



170316-PRE

Prepared by Hershberg & Hershberg HydroCAD® 10.00 s/n 03289 © 2012 HydroCAD Software Solutions LLC

Printed 10/20/2017 Page 2

Area Listing (all nodes)

0.326	74	TOTAL AREA
0.326	74	>75% Grass cover, Good, HSG C (A)
(acres)		(subcatchment-numbers)
Area	CN	Description

Printed 10/20/2017 Page 3

Soil Listing (all nodes)

Area	Soil	Subcatchment
(acres)	Group	Numbers
0.000	HSG A	
0.000	HSG B	
0.326	HSG C	Α
0.000	HSG D	
0.000	Other	
0.326		TOTAL AREA

170316-PRE

Prepared by Hershberg & Hershberg HydroCAD® 10.00 s/n 03289 © 2012 HydroCAD Software Solutions LLC

Printed 10/20/2017

Page 4

Ground Covers (all nodes)

HSG-A	HSG-B	HSG-C	HSG-D	Other	Total	Ground	Subcatchment
(acres)	(acres)	(acres)	(acres)	(acres)	(acres)	Cover	Numbers
0.000	0.000	0.326	0.000	0.000	0.326	>75% Grass cover, Good	Α
0.000	0.000	0.326	0.000	0.000	0.326	TOTAL AREA	

170316-PRE

Prepared by Hershberg & Hershberg HydroCAD® 10.00 s/n 03289 © 2012 HydroCAD Software Solutions LLC

Printed 10/20/2017

Page 5

Pipe Listing (all nodes)

Line#	Node	In-Invert	Out-Invert	Length	Slope	n	Diam/Width	Height	Inside-Fill
	Number	(feet)	(feet)	(feet)	(ft/ft)		(inches)	(inches)	(inches)
1	R1	149.00	139.90	20.0	0.4550	0.015	48.0	0.0	0.0
2	1P	150.00	149.50	30.0	0.0167	0.013	6.0	0.0	0.0

Prepared by Hershberg & Hershberg

HydroCAD® 10.00 s/n 03289 © 2012 HydroCAD Software Solutions LLC

Printed 10/20/2017

Page 6

Time span=0.00-40.00 hrs, dt=0.05 hrs, 801 points
Runoff by SCS TR-20 method, UH=SCS
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment A: Area Runoff Area=14,210 sf 0.00% Impervious Runoff Depth=0.61"

Flow Length=76' Slope=0.0100 '/' Tc=11.5 min CN=74 Runoff=0.26 cfs 0.017 af

Reach R1: 48" PIPE Avg. Flow Depth=0.05' Max Vel=7.89 fps Inflow=0.26 cfs 0.017 af

48.0" Round Pipe n=0.015 L=20.0 S=0.4550 '/ Capacity=839.74 cfs Outflow=0.26 cfs 0.017 af

Pond 1P: Culvert Peak Elev=150.38' Inflow=0.26 cfs 0.017 af

6.0" Round Culvert n=0.013 L=30.0' S=0.0167 '/' Outflow=0.26 cfs 0.017 af

Total Runoff Area = 0.326 ac Runoff Volume = 0.017 af Average Runoff Depth = 0.61" 100.00% Pervious = 0.326 ac 0.00% Impervious = 0.000 ac HydroCAD® 10.00 s/n 03289 © 2012 HydroCAD Software Solutions LLC

Page 7


Summary for Subcatchment A: Area

Runoff = 0.26 cfs @ 12.05 hrs, Volume= 0.017 af, Depth= 0.61"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-40.00 hrs, dt= 0.05 hrs Type II 24-hr 1 YEAR Rainfall=2.50"

_	Α	rea (sf)	CN	Description					
		14,210	74	>75% Gras	>75% Grass cover, Good, HSG C				
_		14,210		100.00% Pe	ervious Area	a			
	Tc (min)	Length (feet)	Slope (ft/ft	•	Capacity (cfs)	Description			
_	11.5	76	0.0100	0.11		Sheet Flow, Grass Grass: Short n= 0.150	P2= 2.60"		

Subcatchment A: Area



Summary for Reach R1: 48" PIPE

[52] Hint: Inlet/Outlet conditions not evaluated

Inflow Area = 0.326 ac, 0.00% Impervious, Inflow Depth = 0.61" for 1 YEAR event

Inflow = 0.26 cfs @ 12.05 hrs, Volume= 0.017 af


Outflow = 0.26 cfs @ 12.05 hrs, Volume= 0.017 af, Atten= 0%, Lag= 0.1 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-40.00 hrs, dt= 0.05 hrs


Max. Velocity= 7.89 fps, Min. Travel Time= 0.0 min Avg. Velocity = 5.97 fps, Avg. Travel Time= 0.1 min

Peak Storage= 1 cf @ 12.05 hrs Average Depth at Peak Storage= 0.05' Bank-Full Depth= 4.00' Flow Area= 12.6 sf, Capacity= 839.74 cfs

48.0" Round Pipe n= 0.015 Brickwork Length= 20.0' Slope= 0.4550 '/' Inlet Invert= 149.00', Outlet Invert= 139.90'



Reach R1: 48" PIPE



Printed 10/20/2017

HydroCAD® 10.00 s/n 03289 © 2012 HydroCAD Software Solutions LLC

Page 9

Summary for Pond 1P: Culvert

[57] Hint: Peaked at 150.38' (Flood elevation advised)

Inflow Area = 0.326 ac, 0.00% Impervious, Inflow Depth = 0.61" for 1 YEAR event

Inflow = 0.26 cfs @ 12.05 hrs, Volume= 0.017 af

Outflow = 0.26 cfs @ 12.05 hrs, Volume= 0.017 af, Atten= 0%, Lag= 0.0 min

Primary = 0.26 cfs @ 12.05 hrs, Volume= 0.017 af


Routing by Stor-Ind method, Time Span= 0.00-40.00 hrs, dt= 0.05 hrs

Peak Elev= 150.38' @ 12.05 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	150.00'	6.0" Round Culvert L= 30.0' Ke= 0.900
			Inlet / Outlet Invert= 150.00' / 149.50' S= 0.0167 '/' Cc= 0.900
			n= 0.013 Flow Area= 0.20 sf

Primary OutFlow Max=0.26 cfs @ 12.05 hrs HW=150.38' (Free Discharge) 1=Culvert (Inlet Controls 0.26 cfs @ 1.65 fps)

Pond 1P: Culvert



Prepared by Hershberg & Hershberg

Printed 10/20/2017

HydroCAD® 10.00 s/n 03289 © 2012 HydroCAD Software Solutions LLC

Page 10

Time span=0.00-40.00 hrs, dt=0.05 hrs, 801 points
Runoff by SCS TR-20 method, UH=SCS
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment A: Area Runoff Area=14,210 sf 0.00% Impervious Runoff Depth=2.21"

Flow Length=76' Slope=0.0100 '/' Tc=11.5 min CN=74 Runoff=1.04 cfs 0.060 af

Reach R1: 48" PIPE Avg. Flow Depth=0.10' Max Vel=11.51 fps Inflow=1.04 cfs 0.060 af

48.0" Round Pipe n=0.015 L=20.0' S=0.4550 '/' Capacity=839.74 cfs Outflow=1.04 cfs 0.060 af

Pond 1P: Culvert Peak Elev=152.18' Inflow=1.04 cfs 0.060 af

6.0" Round Culvert n=0.013 L=30.0' S=0.0167 '/' Outflow=1.04 cfs 0.060 af

Total Runoff Area = 0.326 ac Runoff Volume = 0.060 af Average Runoff Depth = 2.21" 100.00% Pervious = 0.326 ac 0.00% Impervious = 0.000 ac


Summary for Subcatchment A: Area

Runoff = 1.04 cfs @ 12.04 hrs, Volume= 0.060 af, Depth= 2.21"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-40.00 hrs, dt= 0.05 hrs Type II 24-hr 10 YEAR Rainfall=4.80"

_	Α	rea (sf)	CN	Description				
		14,210	74	74 >75% Grass cover, Good, HSG C				
_		14,210		100.00% Pe	ervious Area	a		
	Tc (min)	Length (feet)	Slope (ft/ft)	,	Capacity (cfs)	Description		
	11.5	76	0.0100	0.11		Sheet Flow, Grass Grass: Short n= 0.150	P2= 2.60"	

Subcatchment A: Area



HydroCAD® 10.00 s/n 03289 © 2012 HydroCAD Software Solutions LLC

Printed 10/20/2017

Page 12

D 1 D1 101 D1D

Summary for Reach R1: 48" PIPE

[52] Hint: Inlet/Outlet conditions not evaluated

Inflow Area = 0.326 ac, 0.00% Impervious, Inflow Depth = 2.21" for 10 YEAR event

Inflow = 1.04 cfs @ 12.04 hrs, Volume= 0.060 af

Outflow = 1.04 cfs @ 12.04 hrs, Volume= 0.060 af, Atten= 0%, Lag= 0.1 min


Routing by Stor-Ind+Trans method, Time Span= 0.00-40.00 hrs, dt= 0.05 hrs

Max. Velocity= 11.51 fps, Min. Travel Time= 0.0 min Avg. Velocity = 6.09 fps, Avg. Travel Time= 0.1 min


Peak Storage= 2 cf @ 12.04 hrs Average Depth at Peak Storage= 0.10'

Bank-Full Depth= 4.00' Flow Area= 12.6 sf, Capacity= 839.74 cfs

48.0" Round Pipe n= 0.015 Brickwork Length= 20.0' Slope= 0.4550 '/' Inlet Invert= 149.00', Outlet Invert= 139.90'



Reach R1: 48" PIPE



HydroCAD® 10.00 s/n 03289 © 2012 HydroCAD Software Solutions LLC

Printed 10/20/2017

Page 13

Summary for Pond 1P: Culvert

[57] Hint: Peaked at 152.18' (Flood elevation advised)

Inflow Area = 0.326 ac, 0.00% Impervious, Inflow Depth = 2.21" for 10 YEAR event

Inflow = 1.04 cfs @ 12.04 hrs, Volume= 0.060 af

Outflow = 1.04 cfs @ 12.04 hrs, Volume= 0.060 af, Atten= 0%, Lag= 0.0 min

Primary = 1.04 cfs @ 12.04 hrs, Volume= 0.060 af


Routing by Stor-Ind method, Time Span= 0.00-40.00 hrs, dt= 0.05 hrs

Peak Elev= 152.18' @ 12.04 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	150.00'	6.0" Round Culvert L= 30.0' Ke= 0.900 Inlet / Outlet Invert= 150.00' / 149.50' S= 0.0167 '/' Cc= 0.900 n= 0.013. Flow Area= 0.20 sf

Primary OutFlow Max=1.02 cfs @ 12.04 hrs HW=152.10' (Free Discharge) 1=Culvert (Inlet Controls 1.02 cfs @ 5.17 fps)

Pond 1P: Culvert



Prepared by Hershberg & Hershberg

Printed 10/20/2017

HydroCAD® 10.00 s/n 03289 © 2012 HydroCAD Software Solutions LLC

Page 14

Time span=0.00-40.00 hrs, dt=0.05 hrs, 801 points
Runoff by SCS TR-20 method, UH=SCS
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment A: Area Runoff Area=14,210 sf 0.00% Impervious Runoff Depth=4.04"

Flow Length=76' Slope=0.0100 '/' Tc=11.5 min CN=74 Runoff=1.89 cfs 0.110 af

Reach R1: 48" PIPE Avg. Flow Depth=0.14' Max Vel=13.71 fps Inflow=1.89 cfs 0.110 af

48.0" Round Pipe n=0.015 L=20.0' S=0.4550 '/' Capacity=839.74 cfs Outflow=1.89 cfs 0.110 af

Pond 1P: Culvert Peak Elev=156.66' Inflow=1.89 cfs 0.110 af

6.0" Round Culvert n=0.013 L=30.0' S=0.0167 '/' Outflow=1.89 cfs 0.110 af

Total Runoff Area = 0.326 ac Runoff Volume = 0.110 af Average Runoff Depth = 4.04" 100.00% Pervious = 0.326 ac 0.00% Impervious = 0.000 ac

Page 15


Summary for Subcatchment A: Area

Runoff = 1.89 cfs @ 12.03 hrs, Volume= 0.110 af, Depth= 4.04"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-40.00 hrs, dt= 0.05 hrs Type II 24-hr 100 YEAR Rainfall=7.00"

_	Α	rea (sf)	CN	Description				
		14,210	74	74 >75% Grass cover, Good, HSG C				
_		14,210		100.00% Pe	ervious Area	a		
	Tc (min)	Length (feet)	Slope (ft/ft)	,	Capacity (cfs)	Description		
	11.5	76	0.0100	0.11		Sheet Flow, Grass Grass: Short n= 0.150	P2= 2.60"	

Subcatchment A: Area



HydroCAD® 10.00 s/n 03289 © 2012 HydroCAD Software Solutions LLC

Page 16

Summary for Reach R1: 48" PIPE

[52] Hint: Inlet/Outlet conditions not evaluated

Inflow Area = 0.326 ac, 0.00% Impervious, Inflow Depth = 4.04" for 100 YEAR event

Inflow = 1.89 cfs @ 12.03 hrs, Volume= 0.110 af

Outflow = 1.89 cfs @ 12.03 hrs, Volume= 0.110 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-40.00 hrs, dt= 0.05 hrs

Max. Velocity= 13.71 fps, Min. Travel Time= 0.0 min Avg. Velocity = 6.18 fps, Avg. Travel Time= 0.1 min

Peak Storage= 3 cf @ 12.03 hrs


Average Depth at Peak Storage= 0.14'

Bank-Full Depth= 4.00' Flow Area= 12.6 sf, Capacity= 839.74 cfs


48.0" Round Pipe n= 0.015 Brickwork

Length= 20.0' Slope= 0.4550 '/'

Inlet Invert= 149.00', Outlet Invert= 139.90'



Reach R1: 48" PIPE



Page 17

Summary for Pond 1P: Culvert

[57] Hint: Peaked at 156.66' (Flood elevation advised)

Inflow Area = 0.326 ac, 0.00% Impervious, Inflow Depth = 4.04" for 100 YEAR event

Inflow = 1.89 cfs @ 12.03 hrs, Volume= 0.110 af

Outflow = 1.89 cfs @ 12.03 hrs, Volume= 0.110 af, Atten= 0%, Lag= 0.0 min

Primary = 1.89 cfs @ 12.03 hrs, Volume= 0.110 af


Routing by Stor-Ind method, Time Span= 0.00-40.00 hrs, dt= 0.05 hrs


Peak Elev= 156.66' @ 12.03 hrs

De	evice	Routing	Invert	Outlet Devices
	#1	Primary	150.00'	6.0" Round Culvert L= 30.0' Ke= 0.900 Inlet / Outlet Invert= 150.00' / 149.50' S= 0.0167 '/' Cc= 0.900
				n= 0.013, Flow Area= 0.20 sf

Primary OutFlow Max=1.85 cfs @ 12.03 hrs HW=156.38' (Free Discharge) 1=Culvert (Inlet Controls 1.85 cfs @ 9.41 fps)

Pond 1P: Culvert





Prepared by Hershberg & Hershberg HydroCAD® 10.00 s/n 03289 © 2012 HydroCAD Software Solutions LLC Printed 10/20/2017 Page 2

Area Listing (all nodes)

Area	CN	Description
(acres)		(subcatchment-numbers)
0.326	98	Roofs, HSG A (A)
0.326	98	TOTAL AREA

Prepared by Hershberg & Hershberg HydroCAD® 10.00 s/n 03289 © 2012 HydroCAD Software Solutions LLC

Printed 10/20/2017 Page 3

Soil Listing (all nodes)

Area	Soil	Subcatchment
(acres)	Group	Numbers
0.326	HSG A	Α
0.000	HSG B	
0.000	HSG C	
0.000	HSG D	
0.000	Other	
0.326		TOTAL AREA

Prepared by Hershberg & Hershberg HydroCAD® 10.00 s/n 03289 © 2012 HydroCAD Software Solutions LLC

Printed 10/20/2017 Page 4

Ground Covers (all nodes)

HSG-A (acres)	HSG-B (acres)	HSG-C (acres)	HSG-D (acres)	Other (acres)	Total (acres)	Ground Cover	Subcatchment Numbers
0.326 0.326	0.000 0.000	0.000 0.000	0.000 0.000	0.000 0.000	0.326 0.326	Roofs TOTAL	А
						AREA	

Prepared by Hershberg & Hershberg HydroCAD® 10.00 s/n 03289 © 2012 HydroCAD Software Solutions LLC

Printed 10/20/2017

Page 5

Pipe Listing (all nodes)

Line#	Node	In-Invert	Out-Invert	Length	Slope	n	Diam/Width	Height	Inside-Fill
	Number	(feet)	(feet)	(feet)	(ft/ft)		(inches)	(inches)	(inches)
1	R2	149.00	148.90	20.0	0.0050	0.015	48.0	0.0	0.0

Prepared by Hershberg & Hershberg

Printed 10/20/2017

HydroCAD® 10.00 s/n 03289 © 2012 HydroCAD Software Solutions LLC

Page 6

Time span=0.00-60.00 hrs, dt=0.05 hrs, 1201 points
Runoff by SCS TR-20 method, UH=SCS
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment A: ROOF

Runoff Area=14,210 sf 100.00% Impervious Runoff Depth=2.27"

Flow Length=76' Slope=0.0100 '/' Tc=1.4 min CN=98 Runoff=1.25 cfs 0.062 af

Reach R2: 48" PipeAvg. Flow Depth=0.14' Max Vel=1.42 fps Inflow=0.19 cfs 0.062 af 48.0" Round Pipe n=0.015 L=20.0' S=0.0050 '/' Capacity=88.03 cfs Outflow=0.19 cfs 0.062 af

Pond 1P: ROOF Peak Elev=150.04' Storage=1,331 cf Inflow=1.25 cfs 0.062 af Outflow=0.19 cfs 0.062 af

Total Runoff Area = 0.326 ac Runoff Volume = 0.062 af Average Runoff Depth = 2.27" 0.00% Pervious = 0.000 ac 100.00% Impervious = 0.326 ac HydroCAD® 10.00 s/n 03289 © 2012 HydroCAD Software Solutions LLC

Printed 10/20/2017 Page 7

Summary for Subcatchment A: ROOF


[49] Hint: Tc<2dt may require smaller dt

Runoff = 1.25 cfs @ 11.90 hrs, Volume= 0.062 af, Depth= 2.27"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-60.00 hrs, dt= 0.05 hrs Type II 24-hr 1 YEAR Rainfall=2.50"

A	rea (sf)	CN [Description		
	14,210	98 F	Roofs, HSG	S A	
	14,210	•	100.00% lm	pervious A	Area
Тс	Length	Slope	Velocity	Capacity	Description
(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)	
1.4	76	0.0100	0.89		Sheet Flow, Roof Smooth surfaces n= 0.011 P2= 2.60"

Subcatchment A: ROOF



Printed 10/20/2017

Inflow

Outflow

Page 8

Summary for Reach R2: 48" Pipe

[52] Hint: Inlet/Outlet conditions not evaluated

Inflow Area = 0.326 ac,100.00% Impervious, Inflow Depth > 2.27" for 1 YEAR event

Inflow = 0.19 cfs @ 12.06 hrs, Volume= 0.062 af


Outflow = 0.19 cfs @ 12.07 hrs, Volume= 0.062 af, Atten= 0%, Lag= 0.4 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-60.00 hrs, dt= 0.05 hrs


Max. Velocity= 1.42 fps, Min. Travel Time= 0.2 min Avg. Velocity = 0.69 fps, Avg. Travel Time= 0.5 min

Peak Storage= 3 cf @ 12.07 hrs Average Depth at Peak Storage= 0.14' Bank-Full Depth= 4.00' Flow Area= 12.6 sf, Capacity= 88.03 cfs

48.0" Round Pipe n= 0.015 Brickwork Length= 20.0' Slope= 0.0050 '/' Inlet Invert= 149.00', Outlet Invert= 148.90'



Reach R2: 48" Pipe



Prepared by Hershberg & Hershberg

Printed 10/20/2017

HydroCAD® 10.00 s/n 03289 © 2012 HydroCAD Software Solutions LLC

Page 9

Summary for Pond 1P: ROOF

Inflow Area = 0.326 ac,100.00% Impervious, Inflow Depth = 2.27" for 1 YEAR event

Inflow = 1.25 cfs @ 11.90 hrs, Volume= 0.062 af

Outflow = 0.19 cfs @ 12.06 hrs, Volume= 0.062 af, Atten= 85%, Lag= 9.7 min

Primary = 0.19 cfs @ 12.06 hrs, Volume= 0.062 af

Routing by Stor-Ind method, Time Span= 0.00-60.00 hrs, dt= 0.05 hrs

Peak Elev= 150.04' @ 12.06 hrs Surf.Area= 30,866 sf Storage= 1,331 cf

Plug-Flow detention time= 190.2 min calculated for 0.062 af (100% of inflow)


Center-of-Mass det. time= 191.4 min (945.2 - 753.9)

Volume	In	vert Av	ail.Storage	Storage D	Description		
#1	150	.00'	15,433 cf	Custom	Stage Data (Pri	ismatic)Listed below (Recalc)	
Elevatio (fee		Surf.Area (sq-ft)		c.Store pic-feet)	Cum.Store (cubic-feet)		
150.0 150.5	-	30,866 30,866		0 15,433	0 15,433		
Device	Routing	j l	nvert Ou	tlet Devices			
#1	Primary	/ 15			of drain X 7.00 (

Primary OutFlow Max=0.19 cfs @ 12.06 hrs HW=150.04' (Free Discharge) 1=roof drain (Weir Controls 0.19 cfs @ 0.68 fps)

Page 10

Pond 1P: ROOF



Prepared by Hershberg & Hershberg

Printed 10/20/2017

HydroCAD® 10.00 s/n 03289 © 2012 HydroCAD Software Solutions LLC

Page 11

Time span=0.00-60.00 hrs, dt=0.05 hrs, 1201 points
Runoff by SCS TR-20 method, UH=SCS
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment A: ROOF

Runoff Area=14,210 sf 100.00% Impervious Runoff Depth=4.56"

Flow Longth 76! Sland 0.0400 l// To 1.4 April 6N 0.00 Pure ff 0.420 efe 0.424 efe

Flow Length=76' Slope=0.0100 '/' Tc=1.4 min CN=98 Runoff=2.42 cfs 0.124 af

Reach R2: 48" PipeAvg. Flow Depth=0.21' Max Vel=1.87 fps Inflow=0.47 cfs 0.124 af 48.0" Round Pipe n=0.015 L=20.0' S=0.0050 '/' Capacity=88.03 cfs Outflow=0.47 cfs 0.124 af

Pond 1P: ROOF Peak Elev=150.08' Storage=2,461 cf Inflow=2.42 cfs 0.124 af
Outflow=0.47 cfs 0.124 af

Total Runoff Area = 0.326 ac Runoff Volume = 0.124 af Average Runoff Depth = 4.56" 0.00% Pervious = 0.000 ac 100.00% Impervious = 0.326 ac

HydroCAD® 10.00 s/n 03289 © 2012 HydroCAD Software Solutions LLC

[49] Hint: Tc<2dt may require smaller dt


Runoff = 2.42 cfs @ 11.90 hrs, Volume= 0.124 af, Depth= 4.56"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-60.00 hrs, dt= 0.05 hrs Type II 24-hr 10 YEAR Rainfall=4.80"

A	rea (sf)	CN	Description		
	14,210	98	Roofs, HSG	i A	
	14,210		100.00% Im	pervious A	rea
Tc (min)	Length (feet)	Slope (ft/ft)	,	Capacity (cfs)	Description
1.4	76	0.0100	,	(0.0)	Sheet Flow, Roof Smooth surfaces n= 0.011 P2= 2.60"

Summary for Subcatchment A: ROOF

Subcatchment A: ROOF



HydroCAD® 10.00 s/n 03289 © 2012 HydroCAD Software Solutions LLC

Printed 10/20/2017

Inflow

Outflow

Page 13

Summary for Reach R2: 48" Pipe

[52] Hint: Inlet/Outlet conditions not evaluated

Inflow Area = 0.326 ac,100.00% Impervious, Inflow Depth = 4.56" for 10 YEAR event

Inflow = 0.47 cfs @ 12.05 hrs, Volume= 0.124 af

Outflow = 0.47 cfs @ 12.05 hrs, Volume= 0.124 af, Atten= 0%, Lag= 0.5 min


Routing by Stor-Ind+Trans method, Time Span= 0.00-60.00 hrs, dt= 0.05 hrs

Max. Velocity= 1.87 fps, Min. Travel Time= 0.2 min Avg. Velocity = 0.75 fps, Avg. Travel Time= 0.4 min


Peak Storage= 5 cf @ 12.05 hrs Average Depth at Peak Storage= 0.21'

Bank-Full Depth= 4.00' Flow Area= 12.6 sf, Capacity= 88.03 cfs

48.0" Round Pipe n= 0.015 Brickwork Length= 20.0' Slope= 0.0050 '/' Inlet Invert= 149.00', Outlet Invert= 148.90'



Reach R2: 48" Pipe



Prepared by Hershberg & Hershberg

Printed 10/20/2017

HydroCAD® 10.00 s/n 03289 © 2012 HydroCAD Software Solutions LLC

Page 14

Summary for Pond 1P: ROOF

Inflow Area = 0.326 ac,100.00% Impervious, Inflow Depth = 4.56" for 10 YEAR event

Inflow = 2.42 cfs @ 11.90 hrs, Volume= 0.124 af

Outflow = 0.47 cfs @ 12.05 hrs, Volume= 0.124 af, Atten= 81%, Lag= 8.6 min

Primary = 0.47 cfs @ 12.05 hrs, Volume= 0.124 af

Routing by Stor-Ind method, Time Span= 0.00-60.00 hrs, dt= 0.05 hrs

Peak Elev= 150.08' @ 12.05 hrs Surf.Area= 30,866 sf Storage= 2,461 cf

Plug-Flow detention time= 151.8 min calculated for 0.124 af (100% of inflow)


Center-of-Mass det. time= 153.0 min (893.4 - 740.4)

Volume	In	vert Av	ail.Storage	Storage [Description					
#1	150	.00'	15,433 c	Custom	Stage Data (Pr	ismatic)Listed below (Recalc)				
	Elevation Su		urf.Area In (sq-ft) (cub		Cum.Store (cubic-feet)					
150.00 150.50		,	30,866 30,866		0 15,433					
Device	Routing	j l	nvert Ou	tlet Devices						
#1	Primary	/ 15		3.5" Horiz. roof drain X 7.00 C= 0.600 Limited to weir flow at low heads						

Primary OutFlow Max=0.47 cfs @ 12.05 hrs HW=150.08' (Free Discharge) 1=roof drain (Weir Controls 0.47 cfs @ 0.92 fps)

Page 15

Pond 1P: ROOF



Prepared by Hershberg & Hershberg

Printed 10/20/2017

HydroCAD® 10.00 s/n 03289 © 2012 HydroCAD Software Solutions LLC

Page 16

Time span=0.00-60.00 hrs, dt=0.05 hrs, 1201 points
Runoff by SCS TR-20 method, UH=SCS
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment A: ROOF

Runoff Area=14,210 sf 100.00% Impervious Runoff Depth=6.76"

Flow Length=76' Slope=0.0100 '/' Tc=1.4 min CN=98 Runoff=3.54 cfs 0.184 af

Reach R2: 48" PipeAvg. Flow Depth=0.26' Max Vel=2.15 fps Inflow=0.75 cfs 0.184 af 48.0" Round Pipe n=0.015 L=20.0' S=0.0050 '/' Capacity=88.03 cfs Outflow=0.75 cfs 0.184 af

Pond 1P: ROOF Peak Elev=150.11' Storage=3,462 cf Inflow=3.54 cfs 0.184 af
Outflow=0.75 cfs 0.184 af

Total Runoff Area = 0.326 ac Runoff Volume = 0.184 af Average Runoff Depth = 6.76" 0.00% Pervious = 0.000 ac 100.00% Impervious = 0.326 ac HydroCAD® 10.00 s/n 03289 © 2012 HydroCAD Software Solutions LLC

Page 17

Summary for Subcatchment A: ROOF


[49] Hint: Tc<2dt may require smaller dt

Runoff = 3.54 cfs @ 11.90 hrs, Volume= 0.184 af, Depth= 6.76"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-60.00 hrs, dt= 0.05 hrs Type II 24-hr 100 YEAR Rainfall=7.00"

A	rea (sf)	CN [Description		
	14,210	98 F	Roofs, HSG	S A	
	14,210		100.00% Im	pervious A	vrea
Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
(111111)	(leet)	(11/11)	(11/560)	(CIS)	
1.4	76	0.0100	0.89		Sheet Flow, Roof Smooth surfaces n= 0.011 P2= 2.60"

Subcatchment A: ROOF



HydroCAD® 10.00 s/n 03289 © 2012 HydroCAD Software Solutions LLC

Printed 10/20/2017 Page 18

Summary for Reach R2: 48" Pipe

[52] Hint: Inlet/Outlet conditions not evaluated

Inflow Area = 0.326 ac,100.00% Impervious, Inflow Depth = 6.76" for 100 YEAR event

Inflow = 0.75 cfs @ 12.04 hrs, Volume= 0.184 af


Outflow = 0.75 cfs @ 12.05 hrs, Volume= 0.184 af, Atten= 0%, Lag= 0.6 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-60.00 hrs, dt= 0.05 hrs


Max. Velocity= 2.15 fps, Min. Travel Time= 0.2 min Avg. Velocity = 0.79 fps, Avg. Travel Time= 0.4 min

Peak Storage= 7 cf @ 12.00 hrs Average Depth at Peak Storage= 0.26' Bank-Full Depth= 4.00' Flow Area= 12.6 sf, Capacity= 88.03 cfs

48.0" Round Pipe n= 0.015 Brickwork Length= 20.0' Slope= 0.0050 '/' Inlet Invert= 149.00', Outlet Invert= 148.90'



Reach R2: 48" Pipe



Prepared by Hershberg & Hershberg

Printed 10/20/2017

HydroCAD® 10.00 s/n 03289 © 2012 HydroCAD Software Solutions LLC

Page 19

Summary for Pond 1P: ROOF

Inflow Area = 0.326 ac,100.00% Impervious, Inflow Depth = 6.76" for 100 YEAR event

Inflow = 3.54 cfs @ 11.90 hrs, Volume= 0.184 af

Outflow = 0.75 cfs @ 12.04 hrs, Volume= 0.184 af, Atten= 79%, Lag= 8.1 min

Primary = 0.75 cfs @ 12.04 hrs, Volume= 0.184 af

Routing by Stor-Ind method, Time Span= 0.00-60.00 hrs, dt= 0.05 hrs

Peak Elev= 150.11' @ 12.04 hrs Surf.Area= 30,866 sf Storage= 3,462 cf

Plug-Flow detention time= 133.3 min calculated for 0.184 af (100% of inflow)


Center-of-Mass det. time= 134.4 min (868.9 - 734.5)

Volume	Inv	nvert Avail.Stora		Storage D	Description					
#1	150.	150.00' 15,43		Custom	ismatic)Listed below (Recalc)					
Elevation (feet)		Surf.Area (sq-ft)		c.Store ic-feet)	Cum.Store (cubic-feet)					
150.00 150.50		30,866 30,866		0 15,433	0 15,433					
Device	Routing	outing Invert		let Devices						
#1	Primary	15		3.5" Horiz. roof drain X 7.00 C= 0.600 Limited to weir flow at low heads						

Primary OutFlow Max=0.75 cfs @ 12.04 hrs HW=150.11' (Free Discharge) 1=roof drain (Orifice Controls 0.75 cfs @ 1.61 fps)

Page 20

Pond 1P: ROOF





APPENDIX #2 MAINTENANCE PLAN

Facility Owner (Responsible Party): Harmony Mill South, LLC

The facility owner will be responsible to provide capital funding for this facility. The source will be from infrastructure funds set aside for construction. On an annual basis the responsible party will budget funds to fund the annual operating and maintenance costs. The facility owner must maintain all drainage facilities, stormwater quantity control facilities and all stormwater quality control facilities in accordance with approved plans and with this maintenance manual. Complete inspection form and retain with SWMR. Inspection may be performed by a Qualified Inspector or a Qualified Professional.

The elements of this SWMR which require inspection include:

Roof Drains – Conduct a monthly and quarterly inspection.

Annual inspection shall determine whether the benchmarks listed in the checklist are met.

Operation, Maintenance and Management Inspection Checklist (Complete in 1 Page)

Project: Location:	Location: 90 State Street									
Date: Time: Inspector:	<u></u>									
MAINTENANC	E İTEM	SATISFACTORY(S)/ UNSATISFACTORY(U)	COMMENTS							
1. Cleanout	(Check Monthly)									
Roof areas	On: 90 State Street City of Albany, Albany County, NY Ctor: ENANCE ITEM SATISFACTORY(S)/ UNSATISFACTORY(U) COMMENTS anout (Check Monthly) areas clean of debris									
Area around	Roof Drains is clean	☐ (S) ☐(U)								
	-									
			_							
5. Overall Function of System (Check Annually)										
verify that ro	oot drains are functionin	ig (S) (U)								
Comment	s:									
Actions to	be Taken:									
	Date of Inspec	tion	Sheet 1 of 1							

APPENDIX #3 MAINTENANCE AGREEMENT

STORMWATER MANAGEMENT SYSTEM MAINTENANCE AGREEMENT 90 State Street Apartment Conversion

THIS AGREEMENT ("Agreement") is made and entered into on the	day of	, 2017, by and
between Harmony Mill South, LLC, with an address	(hereii	nafter referred to
as the "Facility Owner"), and		

CITY OF ALBANY, a municipal corporation with an address at 24 Eagle Street, Albany, New York 12207 (hereinafter referred to as the "City").

WITNESSETH:

WHEREAS, the Facility Owner is the owner of the subject parcel of land in the City of Albany, County of Albany and State of New York as more particularly located at 90 State Street, Albany New York.

WHEREAS, the City and the Facility Owner desire that the stormwater management system be built in accordance with the approved project documents and thereafter be maintained, cleaned, repaired, replaced and continued in perpetuity in order to ensure optimum performance of the components; and

WHEREAS, the City has requested this legally binding and enforceable maintenance agreement from the Facility Owner; and

WHEREAS, the Facility Owner is representing the following design documents, with their City approved revisions, as containing all necessary information to construct, operate and maintain the stormwater management system for the lifetime of the facility:

a. Plan submitted to the City representing a stormwater management system including stormwater collection, conveyance and storage using structures designed and specified by Hershberg & Hershberg, Consulting Engineers, sealed by Daniel R. Hershberg, P.E., as the Engineer of Record. The plan sheets showing features associated with the stormwater management system are listed below.

Sheet#	<u>Date</u>	<u>Drawing Title</u>
C-1	9/27/2017	EXISTING CONDITIONS AND SEWER
		CONNECTION PERMIT PLAN

b. STORM WATER MANAGEMENT REPORT (SWMR), 90 State Street Apartment Conversion prepared by Hershberg & Hershberg, Consulting Engineers and Land Surveyors, dated October 4, 2017

IN CONSIDERATION THEREOF, the parties agree as follow:

1. The Facility Owner shall be responsible for maintaining the storm water facility in a manner to prevent silt from becoming tributary to the City's storm water drainage system.

- 2. Operation and maintenance, including inspection and cleaning of the full storm water drainage system, shall be the responsibility of the Facility Owner.
- 3. In the event the Facility Owner fails to maintain the system in a manner to control storm water the City may order the system cleaned and bill the Facility Owner the full cost of this work at labor cost (direct labor plus 50% salary burden) and materials (at cost) if work is performed by the Department of Water & Water Supply; or the cost of a subcontractor plus 10% of the subcontractor's bill if the Department of Water & Water Supply obtains a subcontractor to perform the work. Invoices are payable to the Department of Water & Water Supply within ten (10) business days from the date of invoice. In the event payment for costs is not received within said ten (10) day period, the Department of Water & Water Supply shall have the right to file a lien in the amount of the invoice, together with reasonable costs of collection incurred in connection therewith, against the property of the Facility Owner.
- 4. The City has the right to access the premises for periodic inspections and to perform any maintenance of the stormwater system.
- 5. The Facility Owner shall disclose this Agreement to any successor or assignees in interest.
- 6. This Agreement is binding on the Facility Owner and any successor or assignees in interest hereof.
- 7. Facility Owner agrees to defend, indemnify, and save harmless the CITY and its officers, employees and agents, from and against all claims, actions, causes of action, injuries, damages, losses, liabilities, and expenses (including, without limitation, reasonable attorney's fees and court costs) arising out of, or in consequence of, any negligent or intentional act or omission of Facility Owner to the extent of its or their responsibility for such claims, actions, causes of action, injuries, damages, losses, liabilities, and expenses. The provisions of this Article shall survive any termination or expiration of this Agreement.

[Signatures on next page]

IN WITNESS WHEREOF, the parties hereto have caused this Agreement to be signed by their duly authorized officers as of the day and year first above written.

BY: KATHY M. SHEEHAN MAYOR, CITY OF ALBANY HARMONY MILL SOUTH, LLC STATE OF NEW YORK)) ss.: COUNTY OF ALBANY) On the _ day of______, 201_, before me the undersigned, a Notary Public in and for said State, personally appeared______, personally known to me or proved to me on the basis of satisfactory evidence to be the individual whose name is subscribed to the within instrument and acknowledged to me that he executed the same in his capacity, and that by his signature on the instrument, the individual, or person upon behalf of which the individual acted, executed the instrument. Notary Public STATE OF NEW YORK)) ss.: COUNTY OF_____-)

On the _ day of _______, 201_, before me the undersigned, a Notary Public in and for said State, personally appeared _______, personally known to me or proved to me on the basis of satisfactory evidence to be the individual whose name is subscribed to the within instrument and acknowledged to me that he executed the same in his capacity, and that by his signature on the

instrument, the individual, or person upon behalf of which the individual acted, executed the instrument.

Notary Public

CITY OF ALBANY, NEW YORK

APPENDIX #4 ROOF DRAIN DETAILS

RAINTROL® ROOF DRAINS



control flow to sewers reduce material and labor cost




Fig. 1085

RAINTROL® FLOW CONTROL DRAIN

The RAINTROL® roof drain was developed to offer certain advantageous features. Drains, leaders, storm sewers, etc., can be economically sized by controlling the flow of water. This will reflect in significant cost savings, both in material and labor. In addition, by controlling the drain rate, existing facilities can be utilized without overloading, thus, new construction can be undertaken and tied into the present storm drains.

To accomplish the above, the RAINTROL® drain retains water on the roof. The water is allowed to build up to a predetermined height while the excess is drained off at a known maximum rate. The amount of net build-up is a function of rainfall intensity, time, roof area and drain flow rate. Also note that the flow rate is a function of the build-up or head of water, and not the height of the weir. As an example, water at a 2" depth will flow through either the three inch high or six inch high weir at the same rate.

The area rating, flow rate and drain down time are given for various locations, consistent with the rainfall data for the localities. The data has been established for over 200 localities. Use of this data and tables will allow the engineer to lay out an efficient roof drainage system which will result in significant economies. Local codes must be observed to avoid conflict and approval problems.

THE AREA RATING IS THE MAXIMUM AREA WHICH CAN BE HANDLED BY ONE WEIR OPENING. The corresponding flow rate and drain down time are also given. Data is presented for four

conditions of roof slope and four return periods. This provides data for sixteen conditions for each locality. In cases where the area rating would exceed 25,000 sq. ft., the rating is limited to 25,000 sq. ft. with a resulting lower flow rate and drain down time. Depth or build-up, the other limit upon which the table data is based, is as follows: 3" depth for flat roof, 4" for 2" rise, 5" for 4" rise and 6" for 6" rise.

DATA DERIVATIONS

The data presented is the result of extensive computer processing. Rainfall information obtained from isopluvial maps was computer matched with the flow characteristics of the weir. The results were computer plotted and tabulated in the final pages of tables.

The Weather Bureau Technical Bulletin No. 40, contains the isopluvials which provide the information for the Weiss Equations of Rainfall Intensity. This is more representative than other data available for design purposes. It also covers all areas, not just point locations. The weir equations were developed from test data. When the two equations are solved simultaneously, the area ratings in the tables are produced. Because of the methods employed, extreme accuracy was realized. Fig. 1 is an example of an isopluvial map. Cities along the same isopluvial will have similar rainfall. This allows use of the data for locations which are not listed.

100-YEAR 1-HOUR RAINFALL (INCHES)




Fig. 1

ROOF TYPES

The roof to be drained may vary from flat to a slope of 6" rise. Rise is measured, vertically from the low point or valley to the high point or ridge. (Refer to Fig. 2 below.)

Fig. 2



SLOPED ROOF - DOUBLE RISE

RISE

1

SLOPED ROOF - MULTIPLE RISE


RAINTROL® SPECIFICATIONS

The RAINTROL® drain is offered in two basic designs. The three inch high weir is principally for flat roofs. Though this may be used on sloped roofs, the limited factor is the build up which can not exceed 3". The second design is the six inch weir which can be used on all roofs up to and including a sloped roof with a 6" rise.

NOTE: The roof drains are supplied in increments of weir openings. They are shipped from the factory with the correct weir openings in accordance with the specifications.

However, should some requirements or conditions change, the drain can be adjusted. Vandal proof fasteners prevent unauthorized tampering with the setting.

Included in this section are tables of data for a number of localities. For locations not listed, use values for similar or nearby locations. For specific conditions which require more information, contact Jay R. Smith Mfg. Co.®, Montgomery, Alabama.



DRAIN SYSTEMS

The engineer should lay out the roof drain system consistent with the structural design strength of the roof. Normally for a flat roof with a 30 lb. sq. ft. design load, the water depth or build-up would be limited to 3". This will keep the load down to approximately 15 lbs. per square foot. For sloped roofs, the allowed water depth can be greater, but only to the point where the stresses will be within the design limitations. This will be up to the discretion of the engineer.

The roof drainage design can be based on a number of factors. The prime consideration could be economy, using minimum leaders and storm sewers. The allowable roof load or build-up could limit the design. Or possibly, drain down time could be the limiting design criteria. In any case, knowing the maximum flow rates, which are controlled, the engineer can properly size leaders and storm sewers economically consistent with his selected design criteria.

DESIGN CONSIDERATIONS

When designing the roof drain system, the engineer must remember that the roof is being utilized as a temporary reservoir to retain some water. Flashing and waterproofing should be high enough to prevent any leakage. The engineer must also provide adequate strength for structural safety. In addition, the following considerations should be observed:

- a. On all roofs, use minimum of two drains, if possible.
- On larger roofs, use a greater number of drains as dictated by design layout.
- c. Limit roof area to 25,000 sq. ft. per weir opening.
- d. Recommended maximum distance from roof edge to drain is 50 ft. (flat roofs).
- e. Recommended maximum distance from end of valley to drain is 50 ft. (sloped roofs).
- f. Recommended maximum distance between drains is 200 ft.
- g. Provide adequate flashing at parapets, openings, walls, joints, etc.
- h. Limit parapet walls or provide overflow scuppers. These should be located at the anticipated maximum water depth (build-up). If located in a higher position which could result in a greater flow rate, piping must be sized accordingly.
- Consider wind effect in locating the drains, and the number of drains.
- j. Possible roof deflection due to load. This could create low spots and adversely affect drainage and/or structural safety.

These are not absolute requirements, but are suggestions to be considered. The final design is at the discretion of the design engineer and should be consistent with the roof requirements.

SPECIFYING AND SIZING

A convenient worksheet (Form No. 2052) is available for sizing and determining RAINTROL® requirements. Refer to page 19 for sample.

Specifying can be done quickly and easily.

- Determine roof area to be drained. Each area that is bounded by expansion joints, ridges and any enclosure is considered a separate roof area.
- Divide the roof area by the area rating from the Table of Area Ratings (Table 1) to obtain the total number of weir openings.
- Determine the number of roof drains. This is determined by the engineer and/or roof layout, using the above design consideration as a guide.
- 4. Divide the number of drains into the number of weir openings to obtain the number of weir openings per drain. It is not necessary that all drains have the same number of weir openings. As an example, a roof may require eight weir openings, but only six drains. In this case, four drains could have one weir opening and two drains would have two weir openings.

NOTE: There is a minimum of one weir opening per drain.

Table 1, from which the area rating is selected, also lists the corresponding flow rate and drain down time. With this data, the engineer can select the proper leader and storm sewer to accommodate the flow (Table 3). Scupper or overflow protection must be set at the depth corresponding to the flow rate (Tables 1 and 2). This would limit the potential build-up, flow rate and roof loading. The weir height is the maximum potential build-up. If the scuppers are set at a higher level, the potential build-up would be greater. Leaders and storm sewers would have to be sized for the higher flow rates which correspond to the greater build-up. Also, a greater load might be placed on the roof. Refer to Table 3 on page 1-30 for allowable flow rates. Select leaders and storm sewers, which will accommodate the maximum potential flow.

Local codes may be the determining criteria and deviation must be approved.

TABLES

Table 1 on pages 11 thru 15 is the area rating table for one weir and contains the principal data. It is arranged in alphabetical order by states and cities. The data is divided according to roof type. Example: Flat, 2" 4" or 6" rise. Then four return periods are listed under each roof type. Each block shows three values. The top figure is the area rating, the lower left is the maximum flow rate for the particular area, and the lower right figure gives the corresponding drain down time. The drain down time is based on draining from the maximum depth to a depth of one half inch, which is the practical minimum. (Refer to Fig. 3 below).


For values not shown in Table 1, straight line interpolation will give acceptable figures. Using this table will provide practical solutions. For necessary data not listed, the factory should be contacted. The limits on which Table 1 is based are allowable build-up and maximum area. The build-up limit is 3" for flat roofs, 4" for 2" rise, 5" for 4" rise and 6" for 6"

rise. The area ratings are the square foot areas that will produce the above build-ups. However, if the area rating would exceed 25,000 sq. ft., the area rating was limited to 25,000 and the corresponding maximum flow rate and drain down time recorded. The corresponding build-up can be obtained from Table 2 on page 1-30. Interpolate between values shown when intermediate values are desired.

Table 2 lists flow rates for various heads in 1 inch increments.

Table 3 lists the allowable flow rates for various pipe sizes. Rates are given for vertical leaders, and horizontal storm drains installed at three different slopes. These values are consistent with the National Plumbing Code, and values obtained using Mannings formula.

EXPLANATION OF AREA RATING TABLE 1




AREA RATING TABLE 1 (Continued)

	YPE ROOF ≻		AREA RATING TABLE						BLE	1 (C				6" RISE			
Г	TI E ROOF	AREA RATING SQ. FT.			AREA RATING SQ. FT.			4" RISE AREA RATING SQ. FT.				AREA RATING SQ. FT.					
		FLOW G.P.M.		DRAIN E		FLOW DRAIN DOWN G.P.M. HRS.		FLOW G.P.M.		DRAIN HR		FLOW G.P.M.		DRAIN I HR			
F	RETURN PERIOD>	10 Yr.	25 Yr.	50 Yr.	100 Yr.	10 Yr.	25 Yr.	50 Yr.	100 Yr.	10 Yr.	25 Yr.	50 Yr.	100 Yr.	10 Yr.	25 Yr.	50 Yr.	100 Yr.
	KALAMAZOO	25000 24 46	24900 28 50	15100 28 31	9500 28 19	25000 31 35	25000 36 38	24000 39 39	15100 39 24	25000 40 25	25000 44 28	25000 47 29	20400 49 25	25000 48 20	25000 53 22	25000 56 24	25000 60 25
	MARQUETTE	25000	25000	25000	19800	25000	25000	25000	25000	25000	25000	25000	25000	25000	25000	25000	25000
AN		21 42 25000	25 47 25000	27 49 25000	28 40 16300	28 32 25000	31 35 25000	34 37 25000	37 39 25000	36 23 25000	40 25 25000	42 27 25000	45 28 25000	43 18 25000	47 20 25000	51 21 25000	54 23 25000
MICHIGAN	SAGINAW	22 43	25 47	28 50	28 33	29 33	32 36	35 38	38 40	37 23	41 26	44 28	47 29	45 19	50 21	53 22	56 23
Ē	SAULT STE. MARIE	25000 18 39	25000 21 43	25000 24 46	25000 26 48	25000 25 29	25000 28 32	25000 31 34	25000 33 36	25000 33 21	25000 37 23	25000 39 25	25000 42 26	25000 40 17	25000 44 19	25000 47 20	25000 50 21
	TRAVERSE CITY	25000 21 42	25000 25 47	25000 27 49	19300 28 39	25000 28 32	25000 32 35	25000 34 37	25000 37 39	25000 37 23	25000 40 25	25000 43 27	25000 46 29	25000 44 19	25000 48 20	25000 51 22	25000 55 23
4	AUSTIN	23300	10700	6600	4400	25000	17100	10600	6900	25000	22600	13700	9200	25000	25000	17500	11300
MINNESOTA	DULLITU	28 47 25000	28 22 22800	28 13 13800	28 9 8900	36 39 25000	39 28 25000	39 17 21800	39 11 14100	44 28 25000	49 27 25000	49 17 25000	49 11 18600	53 22 25000	59 25 25000	60 18 25000	60 11 23800
N N	DULUTH	24 47	28 46 13400	28 28 8100	28 18 5200	32 35 25000	36 39 21400	39 35	39 23 8100	40 25	45 28 25000	48 30 17000	49 23 11000	48 20 25000	53 22 25000	57 24 21700	60 24 13600
Σ	MINNEAPOLIS	25000 27 49	28 27	28 16	28 11	34 37	39 34	12700 39 21	39 13	25000 43 27	48 30	49 21	49 13	52 22	57 24	60 22	60 14
	JACKSON	5700 28 12	3400 28 7	2500 28 5	1900 28 4	8900 39 14	5300 39 9	3900 39 6	2900 39 5	11700 49 14	6900 49 8	5000 49 6	3800 49 5	14500 60 15	8500 60 9	6100 60 6	4600 60 5
MISS.	GREENVILLE	6200	3600	2600	1900	9800	5600	4000	2900	12700	7300	5200	3900	15900	9000	6400	4700
Σ	GULFPORT	28 13 2400	28 7 1600	28 5 1300	1000	39 16 3600	39 9 2500	39 6 1900	39 5 1600	49 15 4800	49 9 3300	49 6 2600	49 5 2100	60 16 5800	60 9 3900	60 6 3100	60 5 2600
		28 5 12300	28 3 6100	28 3 4000	28 2 2700	39 6 19500	39 4 9500	39 3 6200	39 3 4200	49 6 25000	49 4 12500	49 3 8200	49 3 5600	60 6 25000	60 4 15700	60 3 10100	60 3 6900
_	COLUMBIA	28 25	28 12	28 8	28 5	39 31	39 15	39 10	39 7	49 30	49 15	49 10	49 7	58 24	60 16	60 10	60 7
MISSOUR	KIRKSVILLE	14200 28 29	6900 28 14	4400 28 9	3000 28 6	22600 39 36	10900 39 18	7000 39 11	4600 39 8	25000 48 30	14300 49 17	9200 49 11	6200 49 8	25000 57 24	17900 60 18	11400 60 11	7500 60 8
MISS	SPRINGFIELD	8700 28 18	4600 28 9	3000 28 6	2100 28 4	13700 39 22	7100 39 11	4700 39 8	3300 39 5	17800 49 22	9300 49 11	6300 49 8	4400 49 5	22600 60 23	11500 60 12	7600 60 8	5300 60 5
-	ST. LOUIS	13600	7200	4700	3300	21500	11200	7400	5100	25000	14600	9800	6800	25000	18600	12100	8200
-	BILLINGS	28 28 25000	28 15 25000	28 10 25000	28 7 25000	39 35 25000	39 18 25000	39 12 25000	39 8 25000	48 30 25000	49 18 25000	49 12 25000	49 8 25000	57 24 25000	60 19 25000	60 12 25000	60 8 25000
	BILLINGS	15 34 25000	19 39 25000	21 43 25000	24 46 25000	23 26 25000	26 30 25000	28 32 25000	31 34 25000	30 19 25000	34 21 25000	37 23 25000	39 25 25000	36 15 25000	41 17 25000	44 19 25000	47 20 25000
	BUTTE	12 28	15 33	17 37	19 40	20 23	22 26	24 28	26 30	27 16	30 19	32 20	34 22	32 13	36 15	39 16	41 17
MONTANA	GLENDIVE	25000 19 40	25000 23 45	25000 26 49	25000 28 40	25000 26 30	25000 31 34	25000 34 37	25000 37 39	25000 35 22	25000 39 25	25000 43 27	25000 46 29	25000 43 18	25000 48 20	25000 52 22	25000 55 23
Νον	GREAT FALLS	25000 15 34	25000 18 39	25000 21 42	25000 23 45	25000 22 26	25000 25 29	25000 27 32	25000 30 34	25000 30 18	25000 33 21	25000 36 22	25000 38 24	25000 35 15	25000 40 17	25000 43 18	25000 46 19
[WAVRE	25000	25000	25000	25000	25000	25000	25000	25000	25000	25000	25000	25000	25000	25000	25000	25000
		17 36 25000	20 42 25000	23 45 25000	26 48 25000	24 27 25000	27 31 25000	30 34 25000	33 36 25000	31 19 25000	35 22 25000	38 24 25000	41 26 25000	37 16 25000	42 18 25000	46 19 25000	49 21 25000
-	MISSOULA	13 30 25000	16 35 25000	18 38 23100	20 41 12000	20 23 25000	23 26 25000	25 29 25000	26 31 19700	27 17 25000	30 19 25000	32 20 25000	35 22 25000	32 14 25000	36 15 25000	39 16 25000	42 18 25000
	CHADRON	21 43	26 48	28 47	28 24	28 32	33 36	36 39	39 32	37 24	42 26	45 28	49 30	45 19	51 21	55 23	59 25
\$	GRAND ISLAND	25000 28 50	9000 28 18	4100 28 8	2000 28 4	25000 38 36	13900 39 22	6500 39 10	3300 39 5	25000 44 28	18800 49 23	8800 49 11	4400 49 5	25000 54 23	23800 60 24	10700 60 11	5300 60 5
NEBRASKA	LINCOLN	16700 28 34	6400 28 13	3500 28 7	2100 28 4	25000 38 40	10400 39 17	5600 39 9	3400 39 5	25000 47 29	13600 49 17	7500 49 9	4400 49 5	25000 56 24	17200 60 17	9200 60 9	5600 60 6
NEB	NORTH PLATTE	25000	15100	6200	2700	25000	23700	9900	4300	25000	25000	13000	5600	25000	25000	16400	6800
		25 47 16500	28 31 6700	28 13 3900	28 5 2400	33 36 25000	39 38 11000	39 16 6300	39 7 3800	42 27 25000	48 30 14200	49 16 8000	49 7 5100	51 22 25000	58 24 18300	60 16 10100	60 7 6300
	OMAHA	28 33	28 14	28 8	28 5 25000	38 40	39 18	39 10	39 6 25000	47 29	49 17	49 10	49 6 25000	56 24	60 18	60 10	60 6 25000
≰	LAS VEGAS	25000 13 28	25000 15 34	25000 17 37	20 41	25000 20 23	25000 22 26	25000 24 28	27 31	25000 27 16	25000 30 19	25000 33 20	35 22	25000 32 13	25000 36 15	25000 39 16	42 18
NEVADA	RENO WIN-	25000 17 37	25000 20 42	25000 23 45	25000 26 48	25000 23 27	25000 26 31	25000 29 33	25000 32 35	25000 30 19	25000 34 21	25000 36 23	25000 39 25	25000 35 15	25000 40 17	25000 43 18	25000 46 20
Ž	NEMUCCA	25000	25000	25000	25000	25000	25000	25000	25000	25000	25000	25000	25000	25000	25000	25000	25000
	BERLIN	10 21 25000	12 26 16000	13 29 11100	14 32 8000	17 18 25000	18 21 25000	20 23 17300	21 25 12300	22 13 25000	25 15 25000	27 16 22900	28 18 15900	27 11 25000	30 12 25000	32 13 25000	34 14 20800
Ξ̈́		27 50 22600	28 32 12400	28 22 8600	28 16 6100	34 37 25000	38 40 19900	39 28 13300	39 20 9500	41 26 25000	46 29 25000	49 28 18200	49 19 12100	49 21 25000	54 23 25000	58 24 22300	60 21 15600
	PORTSMOUTH	28 46	28 25	28 17	28 12	36 38	39 32	39 21	39 15	43 27	49 30	49 21	49 15	51 22	57 24	60 22	60 16
JERSEY	ATLANTIC CITY	11500 28 23	5800 28 12	3900 28 8	2700 28 6	18600 39 30	9300 39 15	6100 39 10	4200 39 7	24500 49 30	12100 49 15	8000 49 10	5600 49 7	25000 58 24	15100 60 15	9900 60 10	6800 60 7
	NEWARK	14900 28 30	7700 28 16	5200 28 11	3600 28 7	24000 39 39	12200 39 20	8100 39 13	5600 39 9	25000 47 29	15800 49 19	10400 49 13	7300 49 9	25000 56 23	19800 60 20	12900 60 13	9000 60 9
NEW	TRENTON	14200	7200	4700	3200	22900	11200	7400	5000	25000	14700	9600	6600	25000	18600	11900	8000
H	ALBUQUERQUE	28 29 25000	28 15 25000	28 10 25000	28 7 25000	39 37 25000	39 18 25000	39 12 25000	39 8 25000	48 29 25000	49 18 25000	49 12 25000	49 8 25000	56 24 25000	60 19 25000	25000	60 8 25000
8		15 34 25000	19 39 25000	21 43 25000	24 46 25000	23 26 25000	26 30 25000	28 32 25000	31 35 25000	31 19 25000	34 21 25000	37 23 25000	40 25 25000	37 15 25000	41 17 25000	44 19 25000	48 20 25000
MEXICO	ALAMOGORDO	17 36	20 42	23 45	26 48	24 28	28 32	31 34	34 37	32 20	36 23	39 25	42 27	39 16	44 19	48 20	51 22
NEW	FARMINGTON	25000 15 34	25000 19 40	25000 22 43	25000 24 46	25000 23 27	25000 26 30	25000 29 33	25000 31 35	25000 31 19	25000 35 22	25000 37 24	25000 40 25	25000 38 16	25000 42 18	25000 45 19	25000 48 20
	ROSWELL	25000 22 43	25000 27 49	18600 28 34	10500 28 21	25000 29 33	25000 34 37	25000 37 39	16900 39 27	25000 37 23	25000 42 27	25000 46 29	22500 49 27	25000 45 19	25000 51 21	25000 55 23	25000 59 25
	ALBANY	25000	17600	11200	7500	25000	25000	17400	11700	25000	25000	23700	15500	25000	25000	25000	19300
	BINGHAMTON	26 48 25000	28 36 18100	28 23 11800	28 15 8000	33 36 25000	38 40 25000	39 28 18100	39 19 12400	41 26 25000	46 29 25000	49 29 24400	49 19 16100	49 21 25000	55 23 25000	59 25 25000	20800
×		26 48 25000	28 37 25000	28 24 24700	28 16 15900	33 36 25000	38 40 25000	39 29 25000	39 20 25000	41 26 25000	46 29 25000	49 30 25000	49 20 25000	49 21 25000	54 23 25000	58 24 25000	60 21 25000
NEW YORK	BUFFALO	22 43	26 48	28 50	28 32	29 33	33 36	36 38	39 40	37 23	41 26	44 28	47 29	45 19	49 21	53 22	56 23
REA	ELMIRA	25000 25 47	21100 28 43	13600 28 28	9300 28 19	25000 32 35	25000 37 39	21200 39 34	14300 39 23	25000 40 25	25000 45 28	25000 48 30	19000 49 23	25000 48 20	25000 53 22	25000 57 24	24300 60 24
	HUNTINGTON	14300 28 29	7700 28 16	5200 28 11	3600 28 7	23000 39 37	12000 39 19	8000 39 13	5600 39 9	25000 47 29	15600 49 19	10400 49 13	7300 49 9	25000 56 24	19700 60 20	13100 60 13	9000 60 9
	JAMESTOWN	25000	25000	21700	14300	25000	25000	25000	22700	25000	25000	25000	25000	25000	25000	25000	25000
	JAIVILO I OVVIN	23 44	27 49	28 44	28 29	30 34	33 37	36 39	39 37	38 24	42 26	45 28	48 30	46 19	50 21	53 22	57 24

MAP POCKET #1

EXISTING CONDITIONS AND SEWER CONNECTION PERMIT PLAN



HERSHBERG HERSHBERG

REVISIONS