

## Demolition Debris Diversion Plan

### 30 Park Ave.

A minimum of 35% of the construction and demolition debris generated by the work of this contract will be diverted from the landfill and recycled or reused. Documentation to support this effort will be required from the demolition contractor before the project begins. A final demolition debris diversion report including weight receipts and disposal destinations will be submitted as part of the contract closeout requirements and before final contract payment is made. Materials including wood, gypsum drywall, metal, concrete, glass windows, can be recycled or reused. We estimate approximately 45 tons of total debris for the project and 17 tons to be diverted from the landfill and recycled or reused.