

260 Sherman Street

Demolition Debris Diversion Plan

- 1) Contract with Demolition Contractor will allow the Demolition Contractor all salvage rights.
- 2) Contractor will remove all accessible metal beams, metal piping, ductwork, and other metal items and remove to demolition contractor's yard for salvage. Estimated 15% of demolition debris volume.
- 3) Contractor will demolish all concrete and masonry walls and crush it in the demolition contractor's yard for sale as fill material. Estimated 23% of demolition debris volume.
- 4) Balance of material will be removed and disposed of at a construction debris landfill.